

CONTRACT ADDENDUM NO. 1

To the Contract Provisions for

**CITY OF MOUNT VERNON PROJECT#
TS-2020-001: 2020 CURB RAMP IMPROVEMENTS**



DATE OF ISSUE: SEPTEMBER 14, 2020

No. of Pages Included in this Addendum: 1

NOTICE TO ALL PLANHOLDERS: This addendum must be inserted into your copy of the contract documents for the above named project.

The following changes, additions, and/or deletions are hereby made a part of the contract documents for the above named project and supersede all previous addenda or other information which may conflict with the information in this addendum.

Item No. 1: Changes to transition panels (Special Provision 8-14.3.4

1. Special Provision 8-14.3.4 which begins "Sidewalk labeled in the plans as "Transition", is deleted and replaced with the following:

Sidewalk labeled in the plans as "Transition" is intended to provide a gradual transition between the slope, dimensions, and elevation of the new and existing sidewalks where the existing sidewalk does not match the requirements of this project. The transition panel shall start at the new sidewalk and shall end at the closest practicable joint in the existing sidewalk while meeting the following requirements:

- A. The cross slope of the transition panel shall be less than or equal to the cross slope of the existing sidewalk at the joint where they meet.
- B. The run slope of the transition panel shall be less than or equal to 4%.
- C. The length of the transition panel shall be no less than 75% and no longer than 150% of the width of the sidewalk unless otherwise shown in the plans. In no case shall the length of the transition panel exceed 8 feet.

Item No. 2: CSTC bedding for sidewalk

All sidewalk shall be underlain with Crushed Surfacing Top Course to a depth of 4 inches. For estimating purposes, the quantity of CSTC provided in the plans is 50% of the required quantity in anticipation that approximately half of the sidewalk will be found to have sufficient existing CSTC.